

UNPRICED BILLS OF QUANTITIES

FOR

FK & JOLAS'S HOME RESIDENTIAL DEVELOPMENT

BABAOBA ROPO OGUNWUSI ESTATE, OFF EDE ROAD, ILE-IFE, OSUN STATE

CLIENT; FAITH AND ANJOLA OLUSOLA KEHINDE

NOVEMBER, 2024

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
A	SUBSTRUCTURE 1.5: EXCAVATING AND FILLING <u>SITE CLEARANCE</u> Clear site vegetation, shrubs and under growth tress, less than or greater than 1.00m girth and uprooting the strut. Dispose off site.		sum		
	<u>EXCAVATION</u> Excavate vegetable top soil average depth 150mm thick and deposited in a temporary spoil heaps maximum distance not exceeding 2.00m deep.	285	m ²		
B	Excavate trench to receive foundation starting from strip level maximum depth not exceeding 2.00m deep	42	m ³		
C	Excavate pit for column base starting from strip level maximum depth not exceeding 2.00m deep	56	m ³		
D	DISPOSAL OF EXCAVATED MATERIAL Dispose of surplus excavated material and other debris offsite		item		
E	Filling obtained from excavated material Final thickness of filling not exceeding 500mm deep 500mm thick; Site, not more than 200mm around site,backfilling foundations; in layers average depth 250mm	57	m ²		
F	Imported Filling; Beds 50mm - 500mm deep 300mm thick; Level, to falls and cross falls	98	m3		
G	Hardcore filling with bolders	33	m3		
	TO COLLECTION				-

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	EXCAVATING AND FILLING (Cont'd)				
	Approved quality 1mm thick damp proof membrane				
A	Damp Proof Membrane; Over 500mm wide, 1mm thick; Horizontal	218	M2		
	1.11: INSITU CONCRETE WORKS				
	Grade 30 Concrete				
B	Mass Concrete; 225mm thick; In trench filling; Poured on or against earth or unblinded hardcore	13	m ³		
	Weak Concrete (1:10 - graded sub base)				
C	Horizontal Work; less or equal to 300 thick; in blinding; poured on or against earth or unblinded hardcore	3	m ³		
	Grade 25 Concrete				
	Horizontal Work				
D	Over 300mm thick; In structures; Reinforced less or equal to 5%. In concrete bed	33	m ³		
E	Over 300mm thick; In structures; Reinforced less or equal to 5%. In col-base	18	m ³	-	-
F	Vertical Work; less or equal to 300mm thick; in structures; Reinforced 5% in column	1	m ³	-	-
	TO COLLECTION				-

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	Formwork				
	Plain formwork				
	<u>Sides of foundations and bases;</u>				
A	Edges of horizontal; less or equal to 500mm high:150mm	81	m		
B	Sides of isolated Columns 18Nr.; Regular rectangular shape	11	m ²		
	Reinforcement				
	<u>High yield steel bars</u>				
C	16mm diameter; Bent; in ground beam	273	kg		
D	12mm diameter; Bent; in column base	430	kg		
E	10mm diameter; Bent; stirups in column	49	kg		
F	Mesh; 4.52kg/sq.m Ref. A152 minimum laps 15	218	m ²		
	1.14: MASONRY				
	Brick/Block Walling				
	<u>460x230x230 mm sandcrete block wall</u>				
	<u>laid in stretcher bond and fill concrete</u>				
	<u>with concrete grade 40</u>				
	<u>Hollow sandcrete blockwall bedded and</u>				
	<u>Walls;</u>				
A	225mm thick; blockwork; skin of hollow walls laid in stretcher bond	81	m ²		
	<u>ADDITIONAL WORK IN SUBSTRUCTURE</u>				
	Allow a provisional sum of N250,000.00(two hundred fifty thousand naira only) for additional work in substructure to be expended, including excavation of rocks may be directed.		Sum		
	TO COLLECTION				-
	<u>COLLECTION</u>				
	Page 1				-
	Page 2				-
	Page 3				-
	TO SUMMARY				-

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	ELEMENT NO 2 FRAME				
	1.11: INSITU CONCRETE WORKS				
	Insitu Concrete				
	Grade 25 Concrete				
	<u>IN-SITU CONCRETE</u>				
	<u>Reinforced in-situ concrete 13.5528,</u>				
	<u>designed mix (1:2:4 19mm aggregate,</u>				
	<u>minimum cement content 300kg/m³</u>				
	<u>vibrated generally in</u>				
A	Horizontal Work; less or equal to 300mm thick; In structures Reinforced less or equal to 5%	14	m ³	-	-
B	Vertical Work; less or equal to 300mm thick; In structures Reinforced less or equal to 5%	6	m ³	-	-
	<u>FORMWORK FOR IN-SITU</u>				
	<u>CONCRETE</u>				
	<u>Sawn formwork of marin boad to vertical</u>				
	<u>side and horizontal bottom of</u>				
C	Beams	167	m ²		
D	Columns	105	m ²		
	<u>REINFORCEMENT FOR IN-SITU</u>				
	<u>CONCRETE</u>				
	<u>Reinforcement bars: 13.e4449 high tensile</u>				
	<u>bar, straight and bend in:</u>				
E	Beams 20mm diameter	441	kg		
F	Beams 16mm diameter	1760	kg		
G	10mm diameter links	1368	kg	-	-
H	Columns 16mm diameter links	887	kg	-	-
J	10mm diameter links	313	kg	-	-
	TO SUMMARY				-

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	ELEMENT NO 4 STAIRCASE				
	1.11: INSITU CONCRETE WORKS				
	Insitu Concrete				
	Grade 25 Concrete				
	<u>IN-SITU CONCRETE</u>				
	<u>Reinforced in-situ concrete 13.5528,</u>				
	<u>designed mix (1:2:4 19mm aggregate,</u>				
	<u>minimum cement content 300kg/m³ vibrated</u>				
	<u>generally in</u>				
A	Horizontal Work; less or equal to 300mm thick; In structures Reinforced less or equal to 5% <u>Sawn formwork to bottom of horizontal</u> <u>work</u>	3	m ³	-	-
B	Sides and soffit of isolated beams; Rectangu Soffit of sloping work; Sloping one way;	3 10	m ² m ²	- -	- -
C	Staircase strings and edges of landing; less or equal to 500mm high:150mm	20	m	-	-
D	Staircase risersl; less or equal to 500mm high:150mm	20	m	-	-
	<u>REINFORCMENT FOR IN-SITU</u>				
	<u>CONCRETE</u>				
	<u>Reinforcement bars: 13.e4449 high tensile</u>				
	<u>bar, straight and bend in:</u>				
E	12mm diameter	250	kg	-	-
	FLOOR FINISHES				
F	40mm thick bed and badking 600×250×10mm vatrified spanish floor	10	m ²		
G	ceramic tiles on benbed squares. <u>15mm thick cement and sand rendering</u>	10	m ²		
	<u>(1:4) steel trowelled on block working</u>				
H	over 600mm wide to bottom of staircase	10	m ²		
	TO SUMMARY				-

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	ELEMENT NO 5				
	ROOF CONSTRUCTION AND COVERING				
	1.11: INSITU CONCRETE WORKS				
	In situ Concrete				
	Grade 25 Concrete				
	Horizontal Work				
	Over 300mm thick; In structures;				
A	Reinforced less or =5%	14	m ³	-	-
	Formwork				
	Plain formwork				
C	Sides and soffit of beams; Rectangular shape	101	m ²	-	-
	High Yield reinforcement Bars				
E	16mm diameter; Straight and bent	1750	kg	-	-
G	10mm diameter;	850	kg	-	-
	1.16: CARPENTRY				
	Timber pressure impregnated with approved preservatives Primary or Structural timber				
	Allow a provisional sum of (1,500,000.00)				
	One Million Five Thousand Naira Only. For				
	cacassing work. To be carried out base on				
	the engineer instruction.		Sum		
	1.17: SHEET ROOF COVERING				
	Sheet Metals				
	0.55mm stone coated aluminium roofing				
	sheet lapped at 0.01m and				
	tied with divided screw nail in the purline				
	Covering over 500mm wide; Sloping 10°				
A	Pitch; oven baked coloured	105	m ²		
B	350mm girth; Ridge cap; Sloping	10	m		
C	150mm girth; Valleys; flashing	72	m		
	TO SUMMARY				-

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	ELEMENT NO: 6				
A	1.14 MASONRY BRICK/BLOCK WALLING Hollow sandcrete blockwall bedded and jointed in cement mortar (1:6) and laid in stretcher bond Walls overall thickness 225mm; Blockwork; Skin of hollow walls; laid in wall	782	m ²		
	TO SUMMARY				-

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	ELEMENT NO: 7				
	WINDOW				
	1.23: WINDOWS SCREENS AND LIGHTS				
	<u>Nigalex or other equal and approved heavy gauge</u>				
	<u>aluminium section two or three bays with net; factory</u>				
	<u>glazed with tinted 4mm thick sheet glass complete with</u>				
	<u>glazing beads and other accessories and ironmongery</u>				
	<u>including screwing and plugging frames to blockwall</u>				
	<u>and concretework to Architects drawings</u>				
	Windows and window frames				
A	1200 X 570mm high	4	Nr		
B	1200 X 875mm high	30	Nr		
C	900 X 875mm high	2	Nr		
D	900 X 950mm high	4	Nr		
E	1200 X 1125mm high	4	Nr		
F	1200 X 1450mm high	2	Nr		
G	900 X 1450mm high	2	Nr		
	<u>window panel and a clear glass panel, non-</u>				
	<u>operable, framed in power coated aluminium</u>				
	<u>finished in light gray (RAL 7016) with</u>				
	<u>Humidity Resistant coating, complete with</u>				
	<u>seals, fasteners, glazing beads and all</u>				
	<u>accessories to manufactueres details and</u>				
	<u>specifications</u>				
H	1200 X 2100mm high	19	Nr		
J	900 x 2100mm high	4	Nr		
K	900x 950mm high	7	Nr		
L	1200 x 2850mm high	8	Nr		
M	1200 x 1800mm high	1	Nr		
N	1595 x 950mm high	1	Nr		
P	1200 x 3000mm high	1	Nr		
Q	1200 x 6600mm high	3	Nr		
R	4270 x 5500mm high	1	Nr		
S	900 x 3000mm high	1	Nr		
T	1200 x 600mm high	1	Nr		
	TO COLLECTION				-

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
A	<u>1.11:IN-SITU CONCRETE</u> <u>Reinforced in-situ concrete 13.5528,</u> <u>designed mix (1:2:4 19mm aggregate,</u> <u>minimum cement content 300kg/m³</u> <u>vibrated generally in</u>				
	Lintels for both doors and windows	3	m ³		
	<u>1.11: FORMWORK FOR IN-SITU CONCRETE</u> <u>Sawn formwork to vertical side and</u> <u>horizontal bottom of</u>				
B	Lintels	39	m ²		
D	<u>1.11: REINFORCEMENT FOR IN-SITU CONCRETE</u> <u>Reinforcement bars: 13.e4449 high tensile</u> <u>bar, straight and bend in:</u>				
	Lintel 12mm diameter	203	kg		
	8mm diameter links	156	kg		
TO COLLECTION					-
COLLECTIONS					
Page 12					-
page 13					-
TO SUMMARY					-

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	ELEMENT NO: 8 DOORS				
	Purpose made swing/sliding doors constructed of hollowsteel sections and steel plates complete with frames and glazing comprising of clear sheet glass and beads including all necessary ironmongery				
	Door Sets				
A	opening size 1200 X 2400mm high; blockwall	1	Nr		
	SINGLE LEAF, SINGLE SWING, PADILLA WOODEN DOOR FINISHED WITH LIGHT GRAY (RAL 7035) HUMIDITY RESISTANT COATING, COMPLETE WITH LOCKS, HINGES, HANDLES, DOORSTOP, DOOR CLOSER AND ALL ACCESSORIES TO MANUFACTURER'S DETAILS AND SPECIFICATIONS				
B	To fit opening size 750 X 2100mm high; blockwall	1	Nr		
C	To fit opening size 800 X 2100mm high; blockwall	8	Nr		
D	To fit opening size 1200 X 2400mm high; blockwall	1	Nr		
E	To fit opening size 2400 X 3000mm high; blockwall	1	Nr		
C	To fit opening size 4800 X 3000mm high; blockwall	1	Nr		
C	To fit opening size 900X 2100mm high; blockwall	11	Nr		
	TO SUMMARY				-

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	ELEMENT NO: 9				
	WALL FINISHINGS				
	1.28: FLOOR WALL CEILING AND ROOF FINISHINGS				
	<u>15mm thick cement and sand rendering (1:4) steel trowelled on block working</u>				
A	over 600mm wide	1632	m ²		
B	Less or equal to 600mm	450	m		
	1.29: DECORATIONS				
	Dulux or other equal and approved latex paint one coat; cement floated wall sandpapered smooth and one coat plastered wall				
	Painting to general surfaces;				
C	less or equal to 300mm girth; internal and external	1245	m ²		
	Painting to general surfaces;				
C	less or equal to 300mm girth; internal and external	450	m		
G	Wall tiles	235	m ²		
	TO SUMMARY				-
	1.28: FLOOR WALL CEILING AND ROOF FINISHINGS				
	<u>Cement and sand mortar (1:4) on concrete base screeded level an to floors only not exceeding 45mm thick to horizontal, to receive ceramic tiles.</u>				
A	40mm thick bed and badking	337	m ²		
B	600×600×10mm vatrified spanish floor ceramic tiles on benbed squares.	337	m ²		
C	Skirtings, net height 100mm; 15mm wide; Blockwall background	463	m		
	TO SUMMARY				-

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>ELEMENT NO: 11</u>				
	CEILING FINISHINGS				
	1.28: FLOOR WALL CEILING AND ROOF FINISHINGS				
	<u>POP ceiling finishes on hardwood noggins including cornice in</u>				
D	POP ceiling internaly	337	m ²		
	TO SUMMARY				-

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>ELECTRICAL INSTALLATIONS</u> <u>V:ELECTRICAL</u> <u>SUPPLY/POWER/LIGHTING</u> <u>INFORMATION</u> Nature and location of the work The work in this section comprises (i) Installation of all work within internal and external faces of building, up to and including distribution boards, cables, light fittings, airconditioners, extractor fans, fire alarms, closed circuit television and communication installations together with associated wiring, conduiting and wall switches. (ii) The description of the measured items are not necessarily fully comprehensive but are intended to indicate the particular item of work concerned. The price for the works allow for conduits, wiring, earthing connection etc. to ensure that the Electrical Installation functions in such a manner as to satisfy all the statutory, regulations of Nigeria and the relevant local government (iv) The rates for fittings are to include for all fixing in any position and at any height and connecting to wiring. (v) All specifications wiring, fitting etc, are in compliance with the Engineer's requirements. (vi) Prime cost and provisional sums are to be expended at the discretions of the Architect where necessary				
		To collection :			30,000.00

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
A	<u>V20 LV DISTRIBUTION</u> <u>Equipment: Metal clad Main Distribution Board as manufactured by MERLIN GERLIN, SIEMENS, ABB, MEM or other approved including bus bars earthing and labels, MCCB links with instructions as specified to form a complete panel installed in accordance with manufacturers instructions</u> Main Switch Boards Free standing cubicle type 100A MV panel complete with encasement; complete with instrumentation indicator lights, voltmeters, ammeter, etc complete with the following <u>Incomers:</u> 100A TPN MCCB with 100A rated busbar <u>Outgoings:</u> 2nr 32A SPN MCCB 1nr 32A Spare with and including installation materials, brackets, neutral link, solid earthing bars	2	nr		
	Switch gears 100Amps 4 pole change over switch <u>DISTRIBUTION BOARDS</u> <u>Metal clad miniature circuit breaker distribution boards; flush wall mounted; stove enamelled sheet steel case and cover with hinged access panel</u>	1	nr		
To collection :					-

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
C	32Amps SP&N mixed capacity MCB type distribution board with integral isolator	2	nr		
	<u>Earth leakage circuit breakers; flush wall mounted; stove enamelled sheet steel case and cover; with manual on/off override switch and test button</u>				
D	32A TP&N ELCB	2	nr		
	<u>PVC; PVC conduit pipe and accessories in wall or concrete including cutting and making good</u>				
	Conduits				
E	25mm diameter	1870	m		
	<u>HV/LV CABLES AND WIRING</u>				
	<u>Cables (Nocaco kabel metal or Nigercin)</u>				
	<u>Cables; copper; PVC insulated and colour coded; in 150mm uPVC pipe (measured separately) in trenches; rate to include for cable connections, cable joints, cable termination glands and all other cable accessories and ancillaries deemed necessary for a complete installation</u>				
G	4c x 16mm ² 1 core pvc/swa/pvc	15	m		
	<u>V21 GENERAL LIGHTING</u>				
		To collection :			

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>Light fittings; ABB or approved equivalent; with specified rated lamps; insulated locations as indicated in electrical drawings; complete with conduit boxes, patresses, roses, flexible cords, starters, chokes, capacitors, lampholders, conduit or chain suspension and all other fittings, accessories and ancillaries necessary for a complete installation.</u>				
A	15w led recessed/ceiling mounted light fitting 6500K (philips)	46	nr		
B	Ceiling mounted chanderlier	14	nr		
C	20w led oval shell bulkhead fitting	27	nr		
D	50W led Security Light	9	nr		
	<u>ACCESSORIES FOR ELECTRICAL SERVICES</u>				
	<u>Plate lighting switches; ABB or approved equivalent; single pole; flush mounted; shuttered whiteplastic cover; galvanized mild steel knock-out box</u>				
F	10A, one - gang, one - way, plate switch.	46	nr		
	<u>Cable and conduits in final circuits; radial main circuits; pvc insulated and colour coded cable to BS 6004 table 1A; drawn into and including 25mm diameter heavy gauge upvc conduit; rate to for all cables and ancillaries deemed necessary for complete installation</u>				
	To collection :				

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>3nr single core 1.50mm2 cables</u>				
H	lighting points	87	nr		
J	switch points	46	nr		
	<u>Power accessories; ABB or approved equivalent; flush mounted; shuttered whiteplastic cover; galvanized mild steel knock-out box fitted with brass earth terminal</u>				
A	13A, double socket outlet plate switch	40	nr		
	<u>CONDUIT AND CABLE TRUNKING</u>				
	<u>Cable and conduits in final circuits; radial main circuits; pvc insulated and colour coded cable to BS 6004 table 1A; drawn into and including 25mm diameter heavy gauge upvc conduit; rate to for all cables and ancillaries deemed necessary for complete installation.</u>				
	<u>3nr single core 2.50mm2 cables</u>				
B	1nr 13A switch socket outlet	40	nr	-	-
	<u>V32 EARTHING AND LIGHTING PROTECTION</u>				
	<u>Ancillaries; supply and install earthing and lighting protection system</u>				
C	Allow for general earth bonding all specialist installations/systems utilizing electric power to the earthing installation		item		
	<u>TESTING AND COMMISSIONING</u>				
D	Testing the entire installation in accordance with the Engineer's specification		item		
		To collection :			

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>Collection</u> <u>ELECTRICAL INSTALLATIONS</u> Page 8/19 Page 8/20 Page 8/21 Page 8/22				-
	To Summary				-
	<u>MECHANICAL INSTALLATIONS INFORMATION</u> <u>Nature and location of the work</u> The work in this section comprises (i.) Sanitary, Drainage and water supply installations, Mechanical services. (ii) The contractor is hereby referred to the Mechanical Services drawing for further details <u>N13 Sanitary Fittings</u> <u>Sanitary fittings in approved colour including assembling all component parts, and making all necessary watertight joints in accordance with the manufacturers instructions, cleaning and leaving in sound mechanical working order on completion (joints to service and waste measured separately)</u>				

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
A	W.C suite comprising pan and "S" trap complete with double flap plastic ring seats with rubber buffers, flushing cistern 9 litres capacity with concealed brackets, including flush bend and rubber cone connector including plugging and screwing cistern to wall	6	nr		
B	Wash hand basin complete with plug, heavy gauge mixers, chain and stay with 12mm chromium plated waste fitting and pair of cantilever brackets cut and pinned to tiled	6	nr		
C	Set of accessories (stainless steel) comprising: Soap dish, Toilet roll holder, Towel rail. hook and cup	6	nr		
D	800mm floor drain; stainless steel; mounted flush with floor finish	6	nr		
	Mirrors				
E	ROSE BUD 6mm silver glass mirror 600x450mm high with chromium plated dome headed screws and polythene buffers.	6	nr		
F	Allow a provisional sum of 5,000,000.00 (Five Million Naira) for VRF FCU Unit A/C to expended and directed by the Architect		item		
G	Water Heater 15ltrs capacity (Aritson)	6	Nr		
H	Extractor fan	6	Nr		
		To collection :			-

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	R11 FOUL DRAINAGE ABOVE GROUND				
	<u>Pipes; straight; uPVC; push-fit jointed; in ducts, chases, floor screeds, and</u>				
A	100mm; waste water pipes and vents; in ducts; fixed to floor, wall and chases	30	m		
B	50mm; waste pipes; in ducts; fixed to floor, wall and chases	20	m		
	Extra over pipework UPVC pipe 100mm				
C	Bend: 100x100mm	12	nr		
D	Tees: 100x100x100mm	6	nr		
E	WC connector sleeve: 100x100mm plus	5	nr		
F	Vent cowl: 100mm	3	nr		
G	Cleanina eve: 100mm	5	nr		
	Extra over pipework UPVC pipe 50mm				
H	Bend: 50x50mm	15	nr		
J	Tees: 50x50x50mm	5	nr		
	S10 COLD WATER				
	PIPE LINES				
	<u>Pipes and fittings heavy gauge multilayer PPR "TECHNOGREEN" types in ducts, trenches, chases, floor screeds and insitu</u>				
K	Water distribution: 25mm in floor and walls	105	m		
L	Water distribution: 20mm in floor and walls	55	m		
		To collection :			-

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	Extra over pipework: PPR pipe: 25mm				
A	Elbow; 25x20mm	20	nr		
B	Tees; 25x20x25mm	13	nr		
C	Sockets; 25mm	15	nr		
D	Nipple; 25x25mm	23	nr		
E	Union connector; 25mm	13	nr		
	Extra over pipework: PPR pipe: 20mm				
F	Elbow; 20x20mm	15	nr		
G	Tees; 20x20x20mm	6	nr		
H	Sockets; 20mm	8	nr	-	-
J	Nipple; 20x20mm	5	nr	-	-
K	Union connector; 20mm	4	nr	-	-
	Accessories for Plumbing Services				
	Valves and Corks; PPR fittings				
L	Gate valve; 25mm	4	nr		
M	Gate valve; 20mm	5	nr		
		To collection :			-

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
A	<u>DRY POWDER/GAS FIRE FIGHTING</u> <u>Equipment; supply, assemble and install the following Angus or approved equivalent equipment in positions indicated on the drawings; rate to include mounting on steel brackets screw to walls fittings</u>				
	Fire extinguisher; hand held for classes ABC; 6kg capacity general purpose dry powder type	2	nr		
	Fire extinguisher; non- conterminated liquid vapour; electrical machine and tools appliances; hand held for classes Co2; 6kg capacity general purpose gas type	2	nr		
B	<u>R12 DRAINAGE BELOW GROUND</u>				
	<u>Y10 PIPELINES</u>				
	<u>PIPELINES; STRAIGHT; TO FALLS; UPLASTICISED PVC PIPES AND FITTINGS; TO B.S. 4660; RUBBER RING LIP SEAL COUPLING JOINTS; CONNECTION TO GULLY TRAPS, CHAMBERS AND MANHOLES (MEASURED SEPARATELY); BURIED IN TRENCHES; AS ENGINEER'S SPECIFICATION</u>				
C	Septic tank overall size 3090mm x 1030mm x 1500mm deep complete with cover slabs.	1			
D	Soakaway pit overall size 1000mm x 1030mm x 1500mm deep complete with cover slabs,	1			

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
		To collection :			-
A	<u>Y11 PIPELINE ANCILLARIES</u> <u>ANCILLARIES AND ASSOCIATED FITTINGS AND ACCESSORIES; FIXING TO PIPEWORK AS SPECIFIED; AS ENGINEER'S SPECIFICATION</u> Accessories in precast concrete; top set in with rodding eye and stopper; cement and sand (1:2) joint to pipe; Inspection chamber size 600x600x600mm deep(average); internally constructed of 150mm plain insert concrete grade 15 base; 150mm plain hollow sandcrete blockwork filled solid with plain concrete and capped with 75mm thick pre-cast concrete grade 20 cover slab reinforced with single layer B.R.C nr 65 mesh ; with 225mm (average) concrete grade 15 benching and forming 150mm half round diameter in and same rendering on sides in water proof cement mortar (1:3) with and including all necessary excavation, earthworks and formwork	7	nr		
		To collection :			-
	<u>Collection</u> <u>MECHANICAL INSTALLATIONS</u> Page 3/19 - Page 3/20 - Page 3/21 - Page 3/22 - Page 3/23 -				
	<u>Carried to Summary</u>				-

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>S PIPED SUPPLY SYSTEMS</u>				
	<u>S10 COLD WATER</u>				
	<u>COLD WATER PIPE LINES</u>				
	<u>Pipes and fittings PPR pipes in trenches as per Engineer's specification, rate to include excavation and fillina</u>				
B	Allow the provisional sum of N550,000.00 (Three Hundred Thousand Naira only) for piping works in relation to external water supply sum to be expended as may be directed by Architect				
	<u>V ELECTRICAL SUPPLY/ POWER/ CCTV/ LIGHTING SYSTEMS</u>				
C	Allow the provisional sum of N.2,000,000.00 (Naira only) for external electrical works; sum to be expended as may be directed by Architect				
D	Allow a provisional sum of 5,500,000.00 for the sinking of borehole complete approved submersible pump 5,000 liters and 3,000 litres overhead tank mounted on 12m structural steel stanchions.				
E					
	Allow a provisional sum of 2,000,000 for landscaping, horticulture and for external works; sum to be expended as may be directed by Architect				
					-

PROPOSED RESIDENTIAL DEVELOPMENT AT ILE IFE OSUN STATE, NIGERIA					
ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<u>GENERAL SUMMARY</u>				
A	Preliminaries				-
B	Main building & Gate House				-
C	Contingency			sum	
	Sub Total				-
	Add VAT 7.5%				-
	GRAND TOTAL				-